



DAV PUBLIC SCHOOL

RAJABAGICHA, CUTTACK - 753009

Ref.No : DAV (RB)/064/2026

Date: 01/06/2026

NOTICE INVITING QUOTATION

Sealed quotations are invited by the undersigned from reputed contractors for the “**RENOVATION OF WASHROOM WALL IN 3RD FLOOR**” of the building at the campus of the school. The interested contractors may submit their quotations for the above purpose obtaining the prescribed quotation format from the office of the undersigned on all working days from 01/06/2026 between 10:30 am to 03:00 Pm. The tender form with the quotation form can be downloaded from school website. The quotation of the same should be sent in a sealed envelope super scribed as “**QUOTATION FOR RENOVATION OF WASHROOM WALL AT 3RD FLOOR**” along with the name and phone number of the contractor on or before 08/06/2026 by 01:00 Pm. The quotation will be opened in the office of the Principal, DAV PUBLIC SCHOOL, RAJABAGICHA, Cuttack at 3:00 Pm on 08/06/2026.

Terms & Conditions

- The quoted rates must be exclusive of GST charges as per applicable
- There should not be any over writing or correction in the quotation form.
- The Undersigned does not bind to accept the lowest quotation and reserves the right to accept the quotation in the whole or in part thereof and reserves the right to cancel any or all the quotations without assigning any reason thereof.
- The quotation received after stipulated date and time or incomplete in any respect shall not be considered.
- The bidder must be present or sent any representative at the time of opening of quotation.


HEADMISTRESS
DAV PUBLIC SCHOOL
RAJABAGICHA, CUTTACK-9

Copy to:

- Notice Board & website of the school for information of all concerned.
- PRINCIPAL, DAV PUBLIC SCHOOL, Cuttack & Bhubaneswar with a request to kindly display on notice board & website for the information to the public concerned
- The Concerned file for record

MANAGED BY - DAV COLLEGE MANAGING COMMITTEE, CHITRA GUPTA ROAD, NEW DELHI

Address - Rajabagicha, Talatelenga Bazar, Cuttack-753009, Phone :- 0671-2349558

Email : dav_rb_ctc@yahoo.co.in, Website : www.davrbctc.org

DAV PUBLIC SCHOOL, RAJABAGICHA

QUOTATION FORM

Date: 01/06/2026

Total Area of Work = 15'0" X 12'0" X 10" = 180 Sqft (Approx)

A. Scope of Work

1. Supply and making bamboo staging up to 4th Floor height from Ground Floor, Netting work with safety belt and other precautionary measures.
2. Dismantling of Damaged brick wall of 15'0" x 12'0 (h)
3. Dismantling of existing corrugated damaged sheets
4. Shifting of Debris from 4th floor to Ground Floor and then shifting of debris outside from campus of School.
5. Re- Brick work of 10" thickness wall from the third floor to fourth floor i.e up to bottom of the channels.
6. Plastering work on both sides of walls and colouring work with complete finishing

B. Rates to be quoted by Bidders for the renovation of the above work

SL	Description of Work	Quantity (approx.)	Unit Rate	Amount (INR)
1	Supply and making the Bamboo Staging Work/Scaffolding work with bamboo ballies, coir rope/wire ties, including labour for erecting, maintenance during execution, dismantling and removal complete as per direction of Engineer-in-charge from existing N.G.L to 4 th Floor (3 rd Floor Roof) from outside portion	690 Sqft		
2	Supply and making the Bamboo Staging Work/Scaffolding work with bamboo ballies, coir rope/wire ties, including labour for erecting, maintenance during execution, dismantling and removal complete as per direction of Engineer-in-charge from existing N.G.L to 4 th Floor (3 rd Floor Roof) from Inside portion	200 Sqft		

3	Dismantling the damaged wall (10" thickness) of 15 ft length and 12' height and shifting of Debris from 3 rd Floor to Ground level(34 Ft)	05 Cum		
4	Fly Ash Brick Masonry in cement mortar (1:6) in Super Structure using Fly Ash bricks of Size 25 x 12 x 8 cm having crushing strength not less than 10 Mpa or 102 Kg/Cm ² , watering and curing after immersing the bricks in water for at least six hours before use including cost, conveyance, royalties, taxes of all materials with labour, cess, T&P required for the work complete in all respect as per direction of Engineer-In-Charge of 15ft length and 12ft height with lifting of materials up to 34 ft height	05 Cum		
5	Plastering: Providing and applying 12-15mm thick cement plaster with cement mortar mix (1:5) with screened and washed sharp sand to the walls with proper finishing complete in all respect including the cost of conveyance, T&P, royalty, taxes etc as per direction of Engineer-In-Charge with lifting of materials from ground floor to 4 th Floor of 15 ft length and 12 ft height (inside portion)	17Sqm		
6	Plastering: Providing and applying 20 mm thick cement plaster with cement mortar mix (1:5) with screened and washed sharp sand to the walls with proper finishing complete in all respect including the cost of conveyance, T&P, royalty, taxes etc as per direction of Engineer-In-Charge with lifting of materials from ground floor to 4th Floor of 15 ft length and 12 ft height (outside portion)	17 Sqm		
7	Colouring Work: Providing and applying two coats of interior Emulsion over one coat of Interior Primer, one coat of cement wash of approved shade, colour with complete finishing in all respect as per direction of Engineer-In-charge. Make: Asian paints (INSIDE PORTION)	17 Sqm		

8	Colouring Work: Providing and applying two coats of interior Emulsion over one coat of Interior Primer, one coat of cement wash of approved shade, colour with complete finishing in all respect as per direction of Engineer-In-charge. Make: Asian paints EXTERIOR PORTION	17 Sqm		
Total Cost for the above work (180 Sqft) approx.				

N.B: GST Charges extra if applicable

The bidder must visit the work site before quoting the rates.

CEMENT used: DALMIA, ULTRATECH, NUVOCO, ACC

No over writing would be done

For any queries, contact: 7008053514 (Pari Prakash Das)

Name of the Contractor with Signature:

Address:

PAN CARD Number with Xerox Attached:

GST Number (If any) with Xerox Attached

Phone no.